

Job Site Preparation

Before Installation

- **All Glazing Is Complete**
Glazing is complete or substantially complete and intact in the area to have work done.
 - **Glazing Is Clear Of Debris And Trash**
No construction materials in contact with glazing - no tape, paint, protection panels, etc. Materials in contact with glazing shall be removed by others and are not the responsibility of the film installer.
 - **Workspace Is Clear**
Move any furniture or equipment to create a minimum 3 ft clear access to the windows on the side receiving the film.
 - **No Dust**
No activity creating dust in the space for 72 hours before install: no sanding, sweeping, grinding, etc.
 - **Caulking Is Dried**
Caulking has dried for at least 48 hours.
 - **Access Behind Fixed Features**
We will do our best in limited access areas. We will provide a sample to show expected result.
-

If Conditions Are Not Met

If instructed to install despite these conditions not being met, it is understood that the application of the glazing film could have a significantly increased amount of airborne contaminants (dust, carpet fibers, etc.) and is at risk for other potential issues that could affect the outcome of the film installation. We cannot be held responsible for issues caused by conditions that do not meet our job-site installation requirements. The contractor agrees that if we install film in dusty conditions, that the additional dust particles trapped under the film will be considered acceptable. We are not responsible for any resulting issues such as: excessive dust or fiber particles trapped under film, or damage to film during the caulking process.

After Installation

Be Mindful Of Work Near The Installed Film

After install, contractor is responsible to protect film. Film needs 30 days to dry and during this period it is critical to be mindful to protect it from tears and damage resulting from dollies, furniture moving, window cleaning, or scraping against the film. The repair or replacement of any film damaged by others is not covered in our scope and there will be a charge to remove and replace.

Signature _____


Lisa M. Chan

Date _____